Rooftop and Pad Mount Pressurization

RTU - 24 - 1 - 2 - X - 15KW - 216 - Press - I - X

Type
RTU - Roof Top Unit
PAD - Pad Unit

1 Ton - 60 Ton

Size/Tonnage
24 = 2 Ton
Others Upon Request

Class N.E.C
1 = Class 1
2 = Class 2

N.E.C Division
1 = Division 1
2 = Division 2

X =Standard "C", "D"
Add A or B for
Groups "A" or "B"

Coating Options
P - Phenicon
H - Hersite
B - Blygold
K - Khemcromik
O - Other

Unit Selection
to be Classified
I - Interior
E - Exterior
IE - Both

Pressurization Type
Press - x
Press -Y
Press -Z

Volts/Phase/Hz
216 - 220/1/60
316 - 380/3/50
236 - 208/3/60
436 - 460/3/60
Others by Request

Electric
Heat
Amount

XPClimate CONTROL
1-866-292-7506